### **ADDENDUM: Product Specs**

Paint: Sherwin Williams ProMar 400 semi-gloss (Color TBD)

Carpet Tile: Aladdin Commercial – Primary Effects Collection or equivalent (Color: TBD)

LVT: Aladdin Commercial – Emergent glue down or equivalent (Color: TBD)

Bathroom Fixtures: American Standard or equivalent

Lights: Lithonia 2x4 LED Basket Troffer or equivalent

Ceiling Fans: Hampton Bay 52" or equivalent

Cove Base/transition: Johnsonite or equivalent (Color: TBD)

Cabinet: Cabinet Wright – Shaker or equivalent (Color: TBD)

Countertops: Formica White Ice Granite Artisan Finish 9476-43 or equivalent. Bullnose edge

**Exterior Doors: Steel** 

#### **ADDENDUM TO PLANS:**

#### **ALL Interior:**

New 4" cove base and carpet to LVT transitions throughout.

- o Replace college provided drop ceiling tiles as needed.
- o Prime and Paint: walls, doors, and trim

# Specs by Legend Number:

- 1 Preschool Room:
  - Cap Floor drains
- 2 No addendums
- 3 No addendums
- 4 No addendums
- 5 Toddler Bathroom:
  - Install (6) 36w36H wall cabinets on West wall (not shown in plans)
- 6 No addendums
- 7 No addendums
- 8 Storage/Laundry/Break Rooms:
  - The West wall that was shown in the plans will not be added in.
  - o Relocate W/D hookups and cabinets according to new layout below
- 9 Adult Bathroom:
  - Remove and close in door opening on East wall (shown in new layout below)
- 10 No addendums
- 11 No addendums
- 12/13/14. Infant Room/Toddler Room/Mixed Group Room
  - Replace (2) existing South exterior doors (Preschool and Infant entrance doors)
  - No ceiling fans needed

## 3. SCHEDULE UPDATES:

- Deadline for receipt of written questions and requests for addenda March 11, 2022
- CCCC responds to questions and/or addenda issued March 15, 2022
- Proposals due 2:00pm Central Time March 21, 2022
- Tentative Notice to proceed March 23, 2022
- \*\*For plumbing, concrete, and electrical details please request a walk-through with Stephanie Downie at (785) 259-2444.

Storage/Laundry/Break Rooms/Adult Bathroom ADDENDUM:

